

## BURIED UTILITY — MAINLINE

# Communications buried mainline and services

Other Town road — Various

Record: 2026-ROW-08

*Public summary — some applicant details omitted*

## APPLICATION RECORD

|                    |                                   |
|--------------------|-----------------------------------|
| Permit number      | 2026-ROW-08                       |
| Submitted          | September 25, 2026 at 4:41 PM CDT |
| Status             | Approved                          |
| Board meeting date | September 29, 2026                |
| Authorized start   | October 1, 2026                   |
| Authorized end     | October 30, 2026                  |

## PROJECT

|                |                                                                                                             |
|----------------|-------------------------------------------------------------------------------------------------------------|
| Permit type    | Buried utility — mainline                                                                                   |
| Public title   | Communications buried mainline and services                                                                 |
| Scope of work  | placing fiber optic in road ROW and crossing road for main and service to customers.                        |
| Traffic impact | Other: off shoulder work, or shoulder work, possible closure if they move equipment from one side to other. |

## LOCATION

|           |                 |
|-----------|-----------------|
| Road      | Other Town road |
| Address   | Various         |
| Geometry  | Multiline       |
| Latitude  | —               |
| Longitude | —               |

## SCHEDULE

|                 |                 |
|-----------------|-----------------|
| Requested start | October 5, 2026 |
| Requested end   | October 5, 2027 |

## PUBLIC CONTACT

|                 |                                         |
|-----------------|-----------------------------------------|
| Organization    | Norvado, Inc                            |
| Contractor      | Tjader & Highstrom Utility Services LLC |
| On-site contact | Brian Hempel                            |

This is a public summary. Applicant contact details are omitted; request the internal record from the Town Clerk under Wis. Stat. ch. 19 if needed.

Town of Winchester · 7228 CTH W, Winchester, WI 54557 · 715-686-2123 · [clerk@winchester.wi.gov](mailto:clerk@winchester.wi.gov)

**PUBLIC CONTACT**

On-site contact phone 715-246-3440

**CONSTRUCTION DETAILS**

Installation method Vibratory plow & Directional bore.

Depth minimum 36"

Road crossings mutiple crossings

Surface Gravel, Paved, asphalt

Width —

Distance to lot line all in ROW, approximatly 3 ft off the back of ROW unless roots ect in way

Slope —

Existing culvert Yes

Existing culvert size N/A

**COMPLIANCE**

Certificate of insurance filed No

Diggers Hotline ticket will call before work starts

Public summary. Generated September 30, 2026 at 06:21 UTC from the Town of Winchester permit tracker.